

(A) Name of Work: Schedule of Quantities for Interior Furnishing works of BAHSUMA Branch with ATM					
S.No.	Description	Qty	Unit	Rate	Amount
<i>Note I : Anti-termite with Chloropyrphos of approved brand and make to be done on all wooden surfaces.</i>					
<i>Note II : Wherever painting items are mentioned, these always include base coats of primer required with a minimum 02 coats of final paint.</i>					
<b>1</b>	<b>BANK COUNTERS</b>				
	a. Providing and fixing front bank counters of 3'-0" wide and 2'-6" height made out of 19 mm thick BWP plywood of Kitply/Natioanal/Greenply with a unit of 3 drawers, one Sliding/ channel with CPU rack and one sliding key board tray in every 4'-6" length with TW foot rest. All the front, and drawer front to be finished with 1mm thick laminate of approved colour. <del>Top should be provided 20 mm thick granite (Black Colour) with 40 mm thick half round moulding of all exposed edges.</del> All internal portion to be finished with enamel painting of approved colour with necessary hardware like brass hinges, -drawer slides, locks and handles for all drawers etc as per instructions.	23.00	Rft		
	b. Providing and fixing barrier partitions (maximum 4' in height at centre) between bank counters in kailwood framework of size 50mm x 50mm at maximum spacing of 600 mm clc both ways with 6 mm thick BWP plywood to both sides finished with 1.5 mm thk laminate, 12 mm thk clear glass with etching of 10mm wide leaving 100mm along all 4 borders of the glass, fixed with beach wood moulded beading as per design above 1.0mt from floor level, fully finished with a bottom skirting. all exposed edges to be provided with TW lipping finished with melamine polish complete as per the drawing and as directed	90.00	Sft		
	c. Providing and fixing 12mm thick glass upright on the front end counter having height of 1 foot supported on steel decorative pipes leaving a gap of 3" between the counter too and bottom of the glass. (23 ft for counters and 13 ft in two rows for Cash Counter).	47.00	Rft		
<b>2</b>	<b>BULK CASH COUNTER</b>				
	Providing and fixing bulk cash counter of 3'-0" width with 2'-6" height on staff side and 3'-10" height on customer side made of 19mm thick BWP grade plywood of Kitply/National/Greenply make with a unit of 3 drawers, one sliding channel with CPU rack and one sliding key board tray in every 4'-6" length with TW foot rest. All exposed surfaces to be finished with 1 mm thk laminate of approved shade & all inernal portions to be finished with enamel painting of approved colour with necessary hardware like brass hinges, drawer, slides, locks and handles for drawers etc as per instructions. <del>Counter Top should be provided with 20mm thick granite (Black color) with 40mm thick moulding on either ends of all exposed sides.</del>	12.00	Rft		
<b>3</b>	<b>CASH ENCLOSURE</b>				
	Cash enclosures of 1.8 M high made of kailwood sections 50mm x 50mm and frame work at maximum 600 mm clc both ways with 6mm thk BWP plywood panelling for both sides and finished with 12mm thk clear glass with 19mm bevelled edges above 1.2m level etched as per design fixed with beachwood beading and finished with melamine polish. With one door of size 0.75mx 1.8m provided with brass hinges, Godrej night latch. brass spring handles, door stopper, door closure etc., as required and as directed.	182.00	Sft		

<b>4</b>	<b>PARTITIONS</b>				
	a. Providing and fixing (maximum 9' 6" in height) partitions in TW framework of size 50mm x 50mm at maximum spacing of 600 mm c/c both ways with 6 mm thk BWP plywood to both sides finished with 1.0 mm thk laminate, fixed with TW moulded beading as per design above 1.0mt from floor level, fully finished with a bottom skirting and wooden cornice of 40mm x 40mm for the top i.e. below the ceiling level and top portion of the cabin, all exposed edges to be provided with TW lipping finished with melamine polish complete as directed.The required wicket gates to be provided in the partition as per the drawing with brass hinges, handles, Godrej locks, door closures etc.(BM CABIN & UPS ROOM)	350.00	Sft		
<b>5</b>	<b>WORKSTATIONS</b>				
	<b>a.Manager Workstation :</b> Providing and Fixing L shaped work station of size 1828 mm length and 460mm deep x 1980 mm length and 750 mm deep with a key board tray, CPU unit, TW foot rest, a unit of drawer in 19mm thk BWP plywood and sides claddd with 12mm thk BWP plywood with teakwood moulding finished in 1.5mm thk laminate of approved colour. with 38 mm x 50 mm TW beading finished with melamine polish, with approved hardware like drawer slides, locks, brass handles etc, internal surfaces to be finished with enamel paint ofl approved shade complete as per drawing and as directed. (BM Cabin)	1.00	Nos		
	<b>b. Officer Workstation :</b> Fixing L shaped work station of size 1350 mm length and 460mm deep x 1500 mm length and 750 mm deep with TW framework of! 50mm x 50mm section and 19mm thk BWP plywood with a key board tray, CPU unit, TW foot rest, a unit of drawer in 19mm thk BWP plywood, with table top of BWP blockboard finished with 1.5 mm thk laminate of approved colour, with 38mm x 50mm TW beading finished with melamine and sides claddd with 12mm thk plywood with teakwood mounting finished in 1.5mm thk laminate and all exposed edges to be finished with TW lipping, with approved hardware like drawer slides, locks, brass handles etc., internal surfaces to be finished with enamel paint of approved shade complete as per drawing and as directed (Advances and Recovery).	2.00	Nos		
<b>6</b>	Providing and fixing WRITING DESK of size 8'x4' feet made up of 19 mm thick commercial board with 6" border.Stand should have 4'x3' pin up board , 10" wide shelf with glass at the top.Bottom portion should be provided with cheque drop box and suggestion box will all necessary fittings and finished with melamine polish etc. complete as per drawing and as directed.	1.0	no		
<b>7</b>	Providing and fixing flap door of size 4' x 3.0' with plywood on wooden framework and finished with matching colour laminate.	12.00	Sft		
<b>8</b>	Providing and fixing 2' x 2' Armstrong tile (12.5 mm thick) false ceiling in aluminium powder coated sections supported with GI framework to the ceiling including proper levelling and finished of the joints and top surface as per manufacturers specifications. All edges shall be perfectly straight G.I. angle shall be embedded within, at the edge, and the surface finished flush with surrounding surfaces complete as directed.	900.00	Sft		

9	Providing and fixing of Gypsum Board false ceiling in aluminium powder coated sections supported with GI framework to the ceiling including proper levelling and finished of the joints and top surface as per manufacturers specifications, All edges shall be perfectly straight GI angle shall be embedded within, at the edge, and the surface finished flush with surrounding surfaces complete as directed.	375.00	Sft		
10	Providing centre table measuring 4' x 2" made up of teak wood with 8mm glass at top.	1.00	Nos		
11	Wall Paneling made out of 2"x1" TW Frame @2ft C/c on both ways with 4"x1" TW member at bottom fixed with nails screw fixed to walls ,columns with wooden plugs wherever required & 4mm Ply with 1mm Sunmica as per approved color etc.(FOR COLUMNS & WALLS)	300.00	sft		
12	Cup-Board made out of 19mm thick comm.Board ,1mm thick sunmica /lamination to be fixed all exposed surfaces (side, top & front). The rate includes necessary hardware such as hinges/tower bolts + shutter + Godrej locks +knobs & Brass Handles . Beading to be polished (melamine) ,all inner surfaces shall be finished with enamel paint two or more coats over a coat of primer.	90.00	sft		
13	Providing and fixing glass door with 12 mmm toughed glass with design as per drawing with patch fittings (Godrej/Ozone/Aura)	72.00	sft		
14	Providing and fixing vertical blinds	75.00	Sft		
15	Providing and fixing ACP for shutter boxing	100.00	Sft		
16	Painting with Texture paint of approved colour wherever required as directed by Engineer Incharge.	500.0	sft		
		<b>Total in Rs.</b>			
		<b>GST____ %</b>			
		<b>Total (including GST) Rs.</b>			