

**TO**  
**CANARA BANK**  
**CIRCLE OFFICE,**  
**AGRA.**  
**BILL OF QUANTITIES / ESTIMATE FOR AC WORK OF**  
**BO: TRANSPORT NAGAR, AGRA.**  
(Including ATM)

S. No.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Supply, Fixing, Testing & commissioning of following star rated AC units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller (Make:- Bluestar / Daikin / LG/ Voltas)				
a)	Cassette 2 TON - INVERTER TECHNOLOGY	Nos	8		
b)	Split 1.5 TON - INVERTER TECHNOLOGY	Nos	1		
c)	Split 1 TON - INVERTER TECHNOLOGY	Nos	2		
2	SITC of interconnecting refrigerant pipe work with closed cell elastomeric nitrile rubber tubular in sulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be peoperly supported with MS hanger & clamps including cabling from indoor to outdoor unit.				
a)	Refrigerant Pipe for 2 TONE AC - INVETER (Cassette)	Rmt	75		
b)	Split 2.0/1.5/1.0 TONE - INVERTER	Rmt	30		
4	SITC of rigid CPVC piping complete with fittings supports as per specification & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
a)	Drain Pipe for 2.0 Tone AC (Cassette)	Rmt	170		
b)	Drain Pipe for Split 2.0/1.5 TR (Split)	Rmt	40		
5	Providing and fixing wall mounted AC out door stand with all accessories.	Set	11		
6	Installation Charges .	Nos	11		
7	Removing of existing centralized AC materials	job	1		
			Total Rs.		
			GST @ 18 %		
	FINAL AMOUNT QUOTED TO BE INCLUDING GST		G. TOTAL		