

BOQ - AC WORKS AT RAH & RO CANARA BANK ETAH

S. No.	DESCRIPTION	QUNTITY.	UNIT	RATE	AMOUNT
1	Supply, Fixing, Testing & comissioning of following star rated AC units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller (Make:- Bluestar / Voltas / Carrier)				
(i)	Cassette 2 TON INVERTER TECHNOLOGY	5.00	No.		
(ii)	Split 1.0 TON - INVERTER TECHNOLOGY	2.00	No.		
2	SITC of interconnecting refrigerant pipe work with closed cell elastomeric nitrile rubber tublar in sulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be peoperly supported with MS hanger & clamps including cabling from indoor to outdoor unit.				
(i)	Refrigerant Pipe for 2 TON AC CASSETTE	60.00	Rmt		
(ii)	Split 2.0/1.5/1.0 TON- INVERTER TECHNOLOGY	30.00	Rmt		
3	Providing & fixing, testing and commissioning of wall mounted copper wound voltage stabilizer suitable for split all accessories. Input Voltage range : 140-280 V, Output : 230 V (Make:- Ruptronics/ Blue- Birds & Reputed Firm .)				
(i)	CAPACITY: 5 KVA	5.00	Nos		
(ii)	CAPACITY: 4 KVA	2.00	Nos		
4	SITC of rigid CPVC piping complete with fittings supports as per specification tions & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
(i)	Drain Pipe for 2.0 Tone AC (Cassette)	50.00	Rmt		
(ii)	Drain Pipe for Split 2.0/1.5 TR (Split)	20.00	Rmt		
5	M.S. stand with monkey case - [In door & out door units]	7.00	No		
6	Installation Charges .	7.00	No		
Total					
GST					
TOTAL INCLUDING GST					
IT IS COMPULSORY TO QUOTE THE RATES INCLUDING GST					