

**BOQ FOR FURNISHING ADDITIONS & ALTERATION WORKS AT CANARA BANK R.A.H SECTION,
FIRST FLOOR, BNC, LUDHIANA.**

| PART-2 : ELECTRICAL WORKS | | | | | |
|---------------------------|---|----------|-------|------|--------|
| S.No. | Item | Quantity | Units | Rate | Amount |
| 1 | UPS POINT WIRING | | | | |
| | Wiring for UPS points with 2x2.50 +1x1.5 sqmm PVC insulated copper conductor wire of 650/1100 volts grade with required earth wire with concealed / exposed PVC pipe, including making all the connections, including cutting chases and making good the surfaces wherever required.including the cost of computer socket board,with 3nos 5Amp 5 pin sockets with1no. 5Amp switch 1no.fuse and 1 no. light indicator with modular swithboard. (max. two points on each circuit, Circuit shall not be paid extra, However cash cabin point & Router point should be indepently fed from single SPMCB of UPS DB) | 7.00 | no. | | |
| 2 | UPSDB: for new tables | | | | |
| | 8 way Double-Door SPN Distribution Board for UPS supply comprising of : | 1.00 | no. | | |
| | 32 Amps DPMCB - 1 Nos. | | | | |
| | 6/10 Amps SPMCB - 6 Nos. | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | TOTAL | | | | |
| | | | | | |