

Prebid meeting for Interior furnishing and allied works on 24th june 2022 for the DRT project to be executed at 4th floor, BSNL building, Rajbhavan Road, Bengaluru

TENDER ref no :BLCPR:ADVSMT:230:2022 dated 18.06.2022

Sl no	Prebid queries	Replies to the queries
01	Time of completion was sought for 75 days by vendors	Finalized the time of completion at 60 days from the date of issue of work orders
02	EMD was not stipulated	1% EMD needs to be submitted at the time of tender submission
03	Armstrong brand False ceiling tiles company is taken over by other company.	Authorisation document for the take over of company needs to be submitted
04	Ply wood grade is mentioned as BWP and MR grade at separate places.	MR grade Ply wood needs to be used Uniformly at all locations.
05	Approved layout is to be provided	Agreed to provide the same
06	In case of vitrified flooring, dado tiles, old tiles to be dismantled and new tiles to be laid or new tiles to be laid on top of existing tiles	Vitrified flooring to be laid on existing tiles using ROFF tile adhesives. Dadoing tiles needs to be dismantled and new tiles to be laid with appropriate cement mortar