

CANARA BANK

INVITATION TO TENDER

ONLY FOR EMPANELLED CONTRACTORS

OF
CIRCLE OFFICE KOLKATA

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

ELECTRICAL WORKS

AT

CANARA BANK – BASUDEVPUR BRANCH

TENDER NO.: 53/23-24/BDS

NAME OF THE CONTRACTOR:

.....

ADDRESS:

.....

SEAL & SIGNATURE OF TENDERER

NOTICE INVITING THE TENDER

To,

M/s

Sealed tenders on item rate basis are invited from panel Contractors for **Electrical Works at BASUDEVPUR Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **22.06.2023 till 30.06.2023.**

Earnest Money Deposit : NIL

Period of completion : 21 days

**Last date, time and place for Submission of tender : On or before 3:00 pm, 30.06.2023 to
The Assistant General Manager,
Premises & Estate section
Canara Bank, Circle Office
Kolkata**

Time and date of opening of tender : 3.30 pm on 30.06.2023

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Assistant General Manager
Premises & Estate Section
Canara Bank, Circle Office
Kolkata**

.....

Date: 22.06.2023

SEAL & SIGNATURE OF TENDERER

GENERAL RULES & INSTRUCTIONS TO TENDERERS

Name of the work: Electrical Works to be carried out at BASUDEVPUR Branch

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 21 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

SEAL & SIGNATURE OF TENDERER

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together weather the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents.

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, electrical wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

TIME PERIOD FOR COMPLETION: 21 days from the date of award of work.
--

SEAL & SIGNATURE OF TENDERER

FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

ESCALATION:

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part thereof if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

ARBITRATION:

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or breach of the contract [other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sole arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as aforesaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as aforesaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the data he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:

**Signature of the Contractor
With seal and address**

SEAL & SIGNATURE OF TENDERER

SCHEDULE OF ELECTRICAL WORKS AT BASUDEVPUR BRANCH					
SL. NO.	ITEM DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	MAIN SWITCH				
	Supply and fixing of Switch Fuse Unit (SFU) with HRC fuse in sheet steel enclosure on M.S. angle frame / M.S. legs on wall complete with interconnection, mending good damages to original finish, painting, etc. as required.				
i)	100 A TPN SFU with HRC fuses	Each.	1		
ii)	63 A TPN SFU with HRC fuses	Each.	2		
2	CHANGE OVER SWITCH (COS)				
	Supply, installation, testing and commissioning of 63A 4P On load front operated change over switch in sheet steel enclosure on M.S legs on wall complete with interconnection, mending good damages to original finish, painting etc. as required.	Each	1		
3	MCB DISTRIBUTION BOARD				
	Supply, installation, testing and commissioning of following MCB Distribution Board in sheet steel enclosure with double door and suitable for mounting on wall by chase cutting and flushed with finished level to the position shown in the Electrical Layout complete in all respect, mending good all damages to the original finish, painting, interconnection, etc. as required. Short circuit I.C. of all MCBs should be 10 KA (minimum) and RCBO should have earth leakage, overload and short circuit protection. Name plate of DB's to be fixed / written on front door alongwith switch board numbers / DB's at the outgoing.				
a)	MAIN DISTRIBUTION BOARD (MDB)				
	TPN 6 way vertical type MCB DB complete with busbar and the following MCBs :				
	Incoming				
	1 no. : 63A 4P MCB Iso.				
	Outgoing :				
	1 no. : 415V,32A TP, MCB				
	6 nos. : 240V, 20-25A SP MCB				

SEAL & SIGNATURE OF TENDERER

	3 nos. : 240V,16A SP MCB				
	Complete board as above	Each.	1		
b)	Lighting Distribution Board (LDB)				
	TPN 4 way vertical type MCB DB complete with busbar and the following MCBs :				
	Incoming				
	1 no. : 40A FP MCB				
	Outgoing :				
	3 Nos. : 25A TP MCB				
	2X32A DPMCB				
	Complete board as above	Each.	1		
d)	12 way Horizontal type SPN DB				
	Incoming :				
	1 No. 32 A DB MCB (20 KA)				
	Outgoing :				
	10x6/10a SPMCB	Each	1		
e)	MCB FOR GLOW SIGN BOARD				
	Supply and fixing of 20A SPN MCB & 20A timmer with 40A DP contractor suitable enclosure on wall for enclosure on wall for Glow Sign board connection.	Each.	1		
4	DISTRIBUTION CABLE :				
a)	SUPPLYING & LAYING OF CABLE :				
	Supplying of 1.1 KV grade following PVC insulated and PVC sheathed armoured aluminium conductor cables conforming of IS:1554 (Part-I) :				
i)	3.5 core 35 Sq.mm.	Mtr.	50.00		
ii)	4 core 16 Sq.mm.	Mtr.	75.00		
c)	CABLE GLAND AND FINISHING THE END				

SEAL & SIGNATURE OF TENDERER

	Supplying and fixing of compression type brass cable gland alongwith rubber rings for dust and moisture proof entry of following 1.1 KV grade aluminium conductor PVC insulated and PVC sheathed armoured cable and finishing the end by crimping method including supply and fixing of "Dowell" make solderless socket, tapes and jointing materials as required to be completed in all respect.				
i)	3.5 core 35 Sq.mm.	Set	2		
ii)	4 core 16 Sq.mm.	Set	6		
5	SUBMAIN WIRING				
	Submain wiring with following sizes 1100 V grade, single core, PVC insulated flexible FRLS copper conductor wire (IS:694) through suitable size PVC. conduit (ISI marked embossed on conduit surface)/ flexible PVC conduit complete with junction box, circular box, elbows, bends and other accessories on surface above false ceiling or concealed by chase cutting on wall/in wooden furnitures, as per site condition, mending good all damages to original finish, interconnection, painting etc. as required to be completed in all respect. All connections of wires to be done by means of "Wago" type connectors:				
i)	With 2 Nos. 6 Sq. mm + 1 No. 2.5 Sq. mm (green colour for earth) PVC insulated Copper wire.(For Glow Sign Board)	Mtr.	100.00		
6	AC POINT WIRING (UPTO 2.0 TON)				
i)	A.C. power point wiring from Main DB to A.C. Power points with 1100 volt grade following rating (Green colour for earthing) PVC insulated flexible FR copper conductor cable through suitable size PVC conduit (ISI marked embossed on conduit surface) complete with junction box, circular box, elbows, bends, couplers and other accessories surfaced on wall above false ceiling or concealed by chase cutting on brick / wooden wall. The work includes supply & fixing by chase cutting on wall, 'North-West' make A.C. power unit having suitable rating socket with plug,plug-top & starter in sheet steel enclosure complete with interconnection, mending good all damages to original finish, painting etc. as required. All				

SEAL & SIGNATURE OF TENDERER

	connections of wires to be done by means of 'Wago' type connectors.				
	With 2 nos. 4 sq.mm. + 1 no. 2.5 sq.mm. (green colour for earth) PVC insulated copper wire in 25 mm dia PVC conduit / casing caping. (for AC unit)	Each.	5		
7	6 /16A SOCKET OUTLET POINT WIRING				
	Power point wiring for 6 pin 6/16 A shuttered socket outle wiring with controlling switch from DB with 1100 volt grade 2 Nos. single core 2.5 sq.mm. + 1 No. 1.5 sq.mm. (Green colour for earthing) PVC insulated flexible FRLS copper conductor wire (IS:694) through suitable size PVC. conduit (ISI marked embossed on conduit surface) complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall. The work includes supply & fixing of modular type 6/16A 6 pin shuttered socket outlet with controlling switch, suitable size mounting box and front plate for socket outlet flushed with finished wall, mending good all damages to original finish, interconnection, painting, etc. as required to be completed in all respect. All connections of wires to be done by means of 'Wago' type connectors.	Each	5		
8	POINT WIRING				
	Point wiring with 1100 V grade 3 nos. single core 1.5 sq.mm. (1 for phase, 1 (black colour) for common neutral by looping method and 1 (green colour) for common earth by looping method) PVC insulated flexible FRLS copper conductor cable (IS:694) through suitable size PVC. conduit (ISI marked embossed on conduit surface) complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall from light & fan switch board to light, fan & 6A socket outlet on the same switch board or separately mounted switch board. The work includes supply and fixing of all materials such as modular type 6A switch for each light and fan point, 6A 2/3 pin shuttered socket outlet with switch, 3 plate ceiling rose / angle or batten				

SEAL & SIGNATURE OF TENDERER

	holder etc. as required.				
	The point wiring also includes circuit wiring with 1100 V grade 2 nos. single core 2.5 sq.mm. (1 for phase and 1 (Black colour) for neutral) + 1 no. single core 1.5 sq.mm. (Green colour for earth) PVC insulated flexible (FRLS) copper conductor cable (IS:694) through suitable size PVC. conduit as described above from DB to switch board, interconnection, mending good all damages to original finish, painting etc. as required to be completed in all respect. All connections of wires to be done by means of "Wago" type connectors. (All wiring in strong room, locker room, records & stationery room will be of surface conduit type).				
i)	1 light control by 1 switch.	Each	33		
ii)	2 light control by 1 switch.	Each	13		
iii)	Wall Bracket fan point with 2/3 pin socket to be installed at fan height and switch at the switch board	Each.	13		
iv)	Ceiling fan point with supply and fixing of 2 module step Regulator (280 W min)	Each	4		
v)	Exhaust fan point	Each	4		
vi)	Call bell point with bell push	Each	1		
vii)	Red light & incandescent light point	Each	1		
viii)	1x6A 2/3 pin shuttered socket with switch on separate switch board other than light / fan switch board	Each	14		
ix)	2/3 pin 6A switch shuttered socket outlet with switch on light and fan switch board.	Each	10		
x	UPS	Each	4		
9	Connecting the main switch to MCB DB by supply and fixing of 6 SWG G.I. wire along the cable with G.I. staples, bolts, nuts, washers, etc. and mending good all damages to original finish.	Mtr.	60.00		
10	Supply and fixing of 16A modular type master controlling switch with indicator in mounting box and front plate on wall for controlling	Each	1		

SEAL & SIGNATURE OF TENDERER

	external light fittings including interconnection, etc. as required.				
11	Earthing (General)				
	Earthing the installation as per I.E Rules conforming to I.S : 3043 - 1987 or its latest ammendment by making earth sation with 3 meter long 50 mm dia G.I earth Pipe (Partly Perforated) to be installed such that its top end shall be at 300 mm below ground level after preparation of ground with charcoal & Salt and connecting with 25 mm x 6 mm G.I earth lead-in-strip upto 10 metre length by bolting and then brazing, complete with nut, bolt, washer etc. as required. The earthing station shall be provided with 300 mm x 300 mm x 300 mm inside dimension masonry inspection Pit with C.I. hinged cover.	Each	2		
12	Extra for earth lead-in-strip exceeding 10 meter as mentioned in above Item with supply and fixing of 25mm x 6mm G.I Strip to be fixed on wall or directly buried in ground including connection complete.	Mtr	22.00		
13	Supplying and fixing of 16 A plug top with 1100 V grade 3 core 2.5 sq. mm PVC insulated copper cable of 1.5 mtr. length one metre to be permanently fixed to the Switch Board of Locker Room, complete in all respects.	Each	1		
14	Supply & fixing of 415V,40A 4P MCB in suitable size M.S. Box same for Light cut off switch in Main Gate.	Each	1		
15	Supply of light and electrical fittings including lamp and all necessary accessories :				
a)	Surface mounted / Suspended luminaries				
i)	1x22 watt Led Light fittings including lamp	Each	20		
16	Recessed mounted luminaries				
i)	LED based luminaries				
	1x32 watt LED based square light fittings with lamp.	Each	15		
ii)	Down lighter				
	1x15 W LED down lighter fittings	Each	17		

SEAL & SIGNATURE OF TENDERER

iii)	1X15W LED light approved make. (for cash counter)	Each	1		
17	Supply of fan fittings with all necessary accessories, but except regulator.				
i)	Wall bracket fan				
	400 mm dia.	Each	13		
ii)	1200 mm ceiling fan	Each	4		
iii)	Exhaust Fan				
	300 mm dia without mounting ring & louver complete	Each	3		
18	SUPPLY & FIXING OF CALL BELLS				
	Supplying and fixing on wall call bell buzzer (approved by Consultant) suitable for 240 volt single phase A.C. supply including interconnection, etc. as required.	Each.	1		
	COMPUTER POWER WIRING				
1	INDUSTRIAL TYPE SOCKET AND PLUG DB				
	Supply and installation of following Legrand make universal mounting DB with Industrial type socket and match plug for UPS incoming & outgoing only :				
i)	32A, 3P+N+E, 5 pin industrial type socket with matching plug and 25A, TP MCB control including interconnection.(for UPS incoming)	Each	2		
ii)	32A, 2P+E, 3 pin industrial type socket with matching plug and 25A, DP MCB control including interconnection.(for UPS outgoing)	Each	2		
iii)	Supply and installation of 2 no 32A 4P on load change over switch, 100A copper busbar, 2 nos 32A SP MCBs etc. in sheet steel enclosure for computer distribution system.	Each	1		
2	COMPUTER DISTRIBUTION BOARD (CDB)				

SEAL & SIGNATURE OF TENDERER

	Supply and installation of following MDS make metallic double door MCB Distribution Board with MCB having short circuit breaking capacity of 10 KA (minimum) and RCBO of 300 mA sensitivity having overload, short circuit and earth leakage protection complete with busbar, interconnection, mounted on flat iron frame on wall/flushed with finished wall by chase cutting, mending good to original finish, painting, etc. as required. Name plate of DB is to be fixed up on front door of DB for its identification.				
	SPN 12 way SPN MCB DB complete with busbar and the following MCBs./ RCBO :				
	INCOMING :				
	1 No. 240 V 25A DP MCB				
	OUTGOING :				
	10 Nos. 240 V 6A SP MCB	Each	2		
3	COMPUTER SOCKET OUTLET CLUSTER POINT WIRING				
	Computer socket outlet cluster point wiring with 1100 V grade 3 nos. single core (1 for earth, green colour) 2.5 sq.mm. PVC insulated flexible FRLS copper conductor cable conforming to IS : 694 through suitable size PVC.conduit (ISI mark embossed on conduit surface) and conduit accessories partly concealed in wall/ embedded in floor, partly on surface above false ceiling and partly through partition or through flexible conduit from DB to computer socket outlet cluster as detailed below and upto connection of 2 nos. socket clusters in 1 (one) circuit connecting by looping method. The work includes supply and fixing of socket outlet clusters component/ sets as detailed below :				
i)	Each computer socket outlet cluster comprising the following :				
	2 nos. 6A 5 pin modular type shuttered socket. (below table)				
	2 no. 6/16A 6 pin modular type shuttered socket. (below table)				
	2 no. 16A modular type controlling switch with indicator. (above table)				
	1 no. Front Plate of suitable size.				
	1 no. Mounting box of suitable size.	Each	14		

SEAL & SIGNATURE OF TENDERER

4	SUBMAIN WIRING :				
	Submain wiring with following size 1100 V grade, single core, PVC insulated flexible copper conductor cable conforming to IS : 694 through PVC.conduit (ISI mark embossed on conduit surface) and conduit accessories partly on surface (above false ceiling) with M.S. bar saddles, partly through partition and partly concealed in wall / embedded in floor by chase cutting, mending good all damages, painting, etc. as required to be completed in all respect.				
i)	From Main DB to UPS Incoming and UPS outgoing to CDB with 2 nos. 6 Sq.mm. + 1 no. 2.5 Sq.mm. (Green colour for earth) PVC insulated flexible copper conductor cable in 25 mm dia. M.S.conduit	Mtr	120.00		
ii)	With 2 nos. 2.5 sq.mm. + 1 no. 1.5 sq.mm. (green colour for earth) PVC insulated copper wire in 20 mm dia PVC conduit / casing capping. (for each computer power point)	Mtr	220.00		
5	EARTHING (COMPUTER)				
	Earthing the installation as per I.E. rules conforming to IS:3043-1987 or its latest amendment by making earth station with 450mm x 450mm x 6mm (minimum) thick copper plate electrode to be installed such that its top edge shall be at a minimum depth of 3.0 metre below ground level after preparation of ground with charcoal and salt and connecting the earth lead-in-wire by bolting and then brazing to the copper plate complete with copper bolts of suitable length double nuts and washers, copper lugs including supply and fixing of 50mm dia. partly perforated G.I. pipe with funnel for watering arrangement.				
i)	The earthing installation should be provided with 300mm x 300mm and 300mm depth inside dimension masonry inspection pit with C.I. hinged cover having locking arrangement and restoring the surfaces duly rammed.	Each	1		

SEAL & SIGNATURE OF TENDERER

ii)	Supplying and fixing of 1 x 10 Sq.mm PVC insulated copper wire through suitable size PVC conduit to be fixed on wall surface with bar saddles / clamps at an interval of 300mm etc. as required to be completed in all respect. The underground portion of earth lead-in-wire to be laid at an average depth of 500 mm below ground level.	Mtr.	30.00		
	TELEPHONE SYSTEM				
1	SUPPLYING AND LAYING OF P.V.C. CONDUIT				
	Supplying and laying of 25mm dia heavy duty rigid PVC conduit (ISI marked embossed on every metre) complete with junction box, circular box, elbows, bends, couplers and other accessories as required by chase cutting on wall embedded in floor or on surface or through partition. The work includes making good all damages to original finish, painting etc. as required.	Mtr.	125.00		
2	TELEPHONE SOCKET				
	Supply and fixing on wall / furniture / partition recessed type MDS/North-West /Anchor woods make Telephone socket outlet (RJ 11) with mounting box & front plate as shown in the drawing complete with chase cutting, mending good etc. as required.	Each	4		
4	TELEPHONE JUNCTION BOX				
	Supply and fixing of 10 pair telephone junction box "Krone" make on wall /furniture/partiion with hinged cover and screwed type tag strips complete with chase cutting, mending good, painting etc. as required.	Each	1		
5	TELEPHONE WIRING				
	Supplying and laying of 2 pair 0.50 mm dia. unarmoured telephone cable through prelaaid rigid PVC conduit as shown in the drawing or otherwise as directed by the consultant from Telephone Junction box to Telephone Socket outlet including interconnection, etc. as required.	Mtr.	125.00		
6	TELEPHONE ARMOURED CABLE				

SEAL & SIGNATURE OF TENDERER

	Supplying and laying of 5 pair 0.50 mm dia armoured telephone cable on wall with M.S bar saddle complete with cable end termination.	Mtr.	30.00		
A	TOTAL EXCLUSIVE OF GST				
B	DISCOUNT IF ANY				
C	TOTAL AFTER DISCOUNT (A - B)				
D	GST				
E	TOTAL INCLUSIVE OF GST (C + D)				
APPROVED MAKE OF MATERIALS					
1	Switch fuse units (HRC)	LEGRAND / INDO-ASIAN / HAVELLS			
2	Timer (TSQ 100)	L & T / HAVELLS			
3	Voltmeter & Ammeter	A. E. / IMP			
4	Voltmeter & Ammeter selector switches	KAYCEE / L & T			
5	Phase indicating lamp	Vaishno / SIEMENS / ROSS controls			
6	Capacitor	CROMPTON/SIEMENS			
7	HRC fuses	GE power / SIEMENS / L & T / SCHNEIDER			
8	Power Cable : XLPE	GLOSTER/POLYCAB/HAVELLS / NICCO			
9	HRC fuse base & carriers.	GE power / SIEMENS / L & T / SCHNEIDER			
10	1.1 KV grade PVC insulated armoured aluminium cable (ISI marked)	GLOSTER / NATIONAL / NICCO / HAVELLS			
11	1.1KV / 600V grade PVC insulated & sheathed / insulated copper wire & flexible cords (ISI marked).	FINOLEX / HAVELLS			
12	RCCB / ELCB / MCCB	LEGRAND / INDO-ASIAN / HAVELLS			
13	Moulded case circuit breaker	LEGRAND / INDO-ASIAN / HAVELLS			
14	RCCB / ELCB	LEGRAND / INDO-ASIAN / HAVELLS			
15	Switch fuse with rewirable fuses. (6A & 32A TPN)	LEGRAND / INDO-ASIAN / HAVELLS			
16	Isolator	LEGRAND / INDO-ASIAN / HAVELLS			
17	Changeover switch (on load type)	LEGRAND / INDO-ASIAN / HAVELLS			
18	MCB distribution board	LEGRAND / INDO-ASIAN / HAVELLS			
19	6/16 Amp modular type switch / flushed type plug socket	ANCHOR (Roma) / CRABTREE / INDO-ASIAN			
20	6/16 Amp modular switch / socket, module plate & mounting M.S. / PVC box.	ANCHOR (Roma) / CRABTREE / INDO-ASIAN			
21	16/25 Amp., 2 module electronic regulator	ANCHOR (Roma) / CRABTREE / INDO-ASIAN			
22	Ceiling rose	KAY / EPP / ANCHOR / JJ			
23	Holder	KAY / EPP / ANCHOR / JJ			
24	Alarm bell	KHERAJ / GETCO			
25	Black enamelled Steel conduits (conforming to IS in all respects)	BEC / SUPREME / AKG			
26	Compression type brass gland	DOWELLS / JOHNSON /			

SEAL & SIGNATURE OF TENDERER

		COMET			
27	Cable termination socket	DOWELL'S			
28	Light fitting & lamps	PHILLIPS / HAVELLS			
29	Ceiling / Wall Mounted Fan	CROMPTON / POLAR / KHAITAN / HAVELL'S			
30	Exhaust fan	CROMPTON / POLAR / KHAITAN / HAVELL'S			
31	Industrial type socket & top	HAVELL'S / CROMPTON / LEGRAND			
32	Telephone wire	FINOLEX / RRK/NATIONAL			
33	Starters	NORTH WEST / CABTREE			
34	All other items not covered above	As per sample approved by Employer/Consultant			

SEAL & SIGNATURE OF TENDERER