

**BOQ - AC WORKS AT RAH CANARA BANK HAPUR**

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	Supply, Fixing, Testing & commissioning of following star rated AC units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller (Make: LG/ Bluestar / Voltas / Carrier Only)				
(i)	Cassette 2 TON - 5 Star	3.00	No.		
(ii)	Split 1.0 TON - 5 Star	2.00	No.		
2	SITC of interconnecting refrigerant pipe work with closed cell elastomeric nitrile rubber tubular in sulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be properly supported with MS hanger & clamps including cabling from indoor to outdoor unit.				
(i)	Refrigerant Pipe for 2 TON AC - 5 Star (Cassette)	25.00	Rmt		
(ii)	Split 2.0/1.5/1.0 TON - 5 Star	15.00	Rmt		
3	Providing & fixing, testing and commissioning of wall mounted copper wound voltage stabilizer suitable for split all accessories. Input Voltage range : 140-280 V, Output : 230 V (Make:- Kiranotics / Logicstate / Creast / Blue- Birds & Reputed Firm .)				
(i)	CAPACITY: 5 KVA	3.00	Nos		
(ii)	CAPACITY: 4 KVA	2.00	Nos		
4	SITC of rigid CPVC piping complete with fittings supports as per specification tions & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
(i)	Drain Pipe for 2.0 Ton AC (Cassette)	30.00	Rmt		
(ii)	Drain Pipe for Split 2.0/1.5 TR (Split)	20.00	Rmt		
5	M.S. stand with monkey case - [ In door & out door units ]	5.00	No		
6	Installation Charges .	5.00	No		
<b>TOTAL (excl.GST) (Rs.)</b>					
<b>*GST extra</b> <b>NOTE -: All work should be done as per Bank's Specification</b>					