

**WORK DESCRIPTION FOR WINDOW REPLACEMENT AT 3<sup>RD</sup> FLOOR CANARA BANK [BOQ]**

**REVISED PRICE BID**

13.04.2021

The GM Cabin, Conference room, DGM cabin, DM cabin and outside DGM cabin area on 3<sup>rd</sup> floor. The specifications of the windows such as Providing and fixing partly fixed and partly openable UPVC casement windows white colour of brand NCL Veka/ Fenesta/ Rehau made out UPVC profiles metre cut and welded. frame duly fixed to masonry wall / concrete slab with 8x100 mm Nylon fastners. The window to have partly fixed glazing and part openable casement windows. The frame should be of 60x55 mm and sash made of 75x60 mm. window should have multi point locking system, handles and hinges. The windows to have glazing of 5 mm clear + 5 mm reflective glass with 1.50 mm PVB layer sandwiched of Saint Gobain/ Indo Ashi/ Modiguard make duly fitted with required TPE gaskets. All installation should be water proof complete with sealing the joints with white neutral grade silicon sealants and all hardware etc as required. The warranty period shall be one year from the date of installation. The work also includes dismantling and removing of existing windows and disposal of same under buyback.

S NO	DESCRIPTION	LENGTH (inches)	BREADTH (Inches)	AREA (SFT)	Rate (Rs.)	Amount (Rs.)
1	DGM CABIN	58	60	24.16		
2	DM CABIN	58	60	24.16		
3	CONFERENCE ROOM	80	168	93.33		
4	CONFERENCE ROOM	80	168	93.33		
5	GM CABIN	80	244	135.56		
6	OUTSIDE DGM CABIN	80	64	35.55		
TOTAL (A)						

Buyback Charges for old window glass with frame (Rs.). [B] .....

Total amount [A] - [B] Rs. ....

In Words .....

GST will be paid Extra as applicable

Sign (Seal) of bidder

