

CANARA BANK

INVITATION TO TENDER

ONLY FOR EMPANELLED CONTRACTORS

OF

CIRCLE OFFICE KOLKATA

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

FURNISHING WORKS

AT

CANARA BANK – MATHABHANGA [4097]

TENDER NO.: 98/22-23/PK

NAME OF THE CONTRACTOR:

.....

ADDRESS:

.....

SEAL & SIGNATURE OF TENDERER



NOTICE INVITING THE TENDER

To,

M/s

Sealed tenders on item rate basis are invited from panel Contractors for **Interior furnishing Works at existing premises of Mathabhanga Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **27.03.2023 till 06.04.2023.**

Earnest Money Deposit : NIL

Period of completion : 30 days

**Last date, time and place for Submission of tender : On or before 3:00 pm, 06.04.2023 to
The Divisional Manager,
Premises & Estate section
Canara Bank, Circle Office
Kolkata**


Time and date of opening of tender : 3.30 pm on 06.04.2023

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Divisional Manager
Premises & Estate Section
Canara Bank, Circle Office
Kolkata**

Date: 27.03.2023

SEAL & SIGNATURE OF TENDERER



GENERAL RULES & INSTRUCTIONS TO TENDERERS

Name of the work: furnishing Works to be carried out at existing premises of Mathabhanga Branch

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 30 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates. .

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.


The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will

SEAL & SIGNATURE OF TENDERER



be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents.

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, Civil & furnishing wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

SEAL & SIGNATURE OF TENDERER .



.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

TIME PERIOD FOR COMPLETION: 30 days from the date of award of work.

FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

ESCALATION:

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement,

SEAL & SIGNATURE OF TENDERER



after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of in any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

ARBITRATION:


All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or breach of the contract [other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sole arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as aforesaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as aforesaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

SEAL & SIGNATURE OF TENDERER .



If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

The arbitrator shall be deemed to have entered on the reference the date he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.


Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:


**Signature of the Contractor
With seal and address**

SEAL & SIGNATURE OF TENDERER



APPROVED MAKE OF MATERIALS		
1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti - termite Treatment.	Malaysian Sal / Kapoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Cedar / CP Teak
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by British Paint
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWR Ply (IS : 710)	Century / Green/ Sylvan/ Globe
7	Flush Door / BWP Block board (IS : 1659)	Century / Green / Sylvan / Globe
8	Laminate (1.0 mm thk.) (IS : 2046)	Green lam / Century mica / Sunmica (Aica) / Airolam
9	Door Closure (Heavy Duty)	Godrej / Archi / Sterling (DC 2000)
10	Floor Spring (Heavy Duty)	Godrej / Archi / Sterling (FS 3000)
11	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock (Multipurpose)	Ebco / Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF
18	Sliding Telescopic Drawer Channel	Ebco / Earl Behari / Efficient Gadjets
19	Cable Organizer	Ebco / Innofitt Systems (CM 63.C)
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi / AIS / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Birla
26	Texture Paint	Spectrum
27	Glass	Modi / AIS / Saint Gobain
28	European WC / Washbasin	Hindware /Parryware
29	Sanitary Fittings	Jaquar / Essco Delux
30	G.I. Pipe	Tata (Medium)
31	Cement	Ultratech / Lafarge / ACC
32	Footmat	Birla 3M / Approved Equivalent
33	Vitrified Tiles	Johnson / Naveen / Kajaria
34	Ceramic Tiles	Johnson / Naveen / Kajaria
35	All other items not covered above	As per sample approved by Employer/Consultant


SEAL & SIGNATURE OF TENDERER



CANARA BANK, MATHABHANGA BRANCH, COOCHBEHAR					
TENDER FOR ELECTRICAL WORK					
SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Distribution wiring in 2x22/.3(1.5 sqmm)single core stranded 'FR' PVC insulated & unsheathed copper wire (approved make) in 20mm size PVC rigid conduit 'FR' (precision make) with 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire ECC with all accessories embeded in wall/ceiling, to light/fan/call bell points with Modular type switch fixed on GI switch board on wall complete with 2 no. suitable size "Ph & N" copper bar with holes fixed on bakelite/hard rubber insulation over the JB welded chairs incl. Modular (wall matching colour) top cover 3 mm thick and incl. suitable size inspection box making earthing attachment painting the GI box and mending good the damages.	60	Pts.		
2	Distribution wiring in 1.1 KV grade 2x22/.3(1.5 sqmm)single core stranded 'FR' PVC insulated & unsheathed copper wire (approved make) in 20mm size PVC rigid conduit 'FR' (precision make) with 1.1 KV grade 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC with all accessories embeded in wall, to 6 A modular socket & Modular type switch fixed on GI switch board incl. modular (wall matching colour) top cover 3mm thick and incl. painting the GI box and mending good the damages to original finish.	15	Pts.		
3	Supply fixing & connection light fittings/fans:				
a	2' LED TUBE 8W or Similar approved of Philips/ Havells/ Crompton Greaves .(with all accessories)	4	Each		
b	Supplying and fixing of call bell with modular type push complete with plate and box to be fixed and mending good all damages.	1	Each		
c	12W 150mm Dia round down light or Similar approved of Philips/ Havells/ Crompton Greaves (Surface mounted LED downlight).(Some lights should connected with UPS as necessary at site)	25	Each		
d	36W LED 2'X2' Square light or Similar approved of Philips/ Havells/ Crompton Greaves (High efficiency Surface mounted LED luminaire).(Some lights should connected with UPS as necessary at site)	13	Each		
e	Supply and fixing of 400mm 230V oscillating type Wall mounted Bracket fan to be fixed on wall with allied arangement. Havells(Plantina)/ Usha/Bajaj make with all accessories.	10	Each		
f	Supply,erection and connection of 6" PVC exhaust fan Louvers Type Including Wall Cutting with Mending damages & Painting etc as required (Havells/Usha/Bajaj) make.	4	Each		



SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
4	TELEPHONE WIRING				
a	Supply and fixing of telephone junction box "Krone/Henzel" make on wall /furniture/partition with hinged cover and screwed type tag strips complete with mending good,painting etc as required	1	Each		
b	Supply and erection of modular type telephone outlet RJ 11 mounted on suitable plate housed in recessed MS box (Make - TATA TELECOM / SIEMENS / LUCENT)	2	Each		
c	Supplying, Installation, Testing & Commissioning of 10 pair 0.51 sq. mm. telephone unarmoured cable in 20 mm PVC pipe. (Make - Finolex / Havells / Polycab)	50	mtr		
5	COMPUTER DATA SYSTEM/LAN WIRING				
a	Supplying and laying of CAT-6 cable through suitable size PVC casing capping from server to HUB,HUB to Computer Data Socket including interconnection mending good etc. as required (Make - Havells / Finolex / Polycab/ KEI)				
b	Supply and fixing on wall/furniture/partition recessed non-modular type Computer data socket (D-Link make) with mounting box & front plate as shown in the drawing complete with mending good etc. as required. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand) (For BM-2 points)				
6	MAIN LINE WIRING				
a	Supply and laying 4x10 sqmm+1x6sqmm PVC insulated copper wire from Panel board to LDB (Make - Havells / Finolex / Polycab/ KEI)	15	mtr		
b	Supply and laying 2x6sqmm+1x4sqmm PVC insulated copper wire from Panel board to CDB (Make - Havells / Finolex / Polycab/ KEI)	15	mtr		
c	Supply and laying 2x4sqmm+1x2.5sqmm PVC insulated copper wire from TPN MCB DB to power plug (Make - Havells / Finolex / Polycab/ KEI)	100	mtr		
d	Supply and laying 2x2.5sq.mm+1x1.5sqmm pvc Insulated copper wire from SPN MCB DB to switch boards (Make - Havells / Finolex / Polycab/ KEI)	180	mtr		
e	Supply and laying 2x16sq.mm+1x10sqmm pvc insulated copper wire (Make - Havells / Finolex / Polycab/ KEI)	40	mtr		
f	Supplying and fixing 250V 6 pin 16A modular plug socket with 16A modular switch and earthing attachment incl. S&F sheet GI box, modular plate and necessary earthing attachment. (Make - L&T/ Anchor-Panasonic/ Crabtree/ Legrand)	8	Each		
7	RAW POINT WIRING				
	Supply and laying 2x6sqmm+1x4sqmm PVC insulated copper wire (MCB DB TO RAW POINT) (Make - Havells/ Finolex/ Polycab/ KEI)	90	mtr		



SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
8	OUT DOOR TYPE GLOW BOARD WIRING				
a	Supply laying of main line with 2x2.5 +1x1.5 sqmm through MS conduit from main panel to glow sign board.(Make - Havells/ Finolex/ Polycab/ KEI)	30	mtr		
b	Supply & fixing of glow sign board programmable timer switch 24 hrs . (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	1	No.s		
9	UPS WIRING				
a	Supply fixing & connection of UPS circuit line with 1.1kv grade PVC Insulated non sheathed stranded copper cable of (FRILS) with 2x2.5sqmm+1x1.5sqmm through rigid PVC conduit 20 mmdia 1.6mm wall thickness, with ISI marks, to lay from UPS MCB DB to plug point board. Two nos point to be connected from One circuit. (Make - Havells /Finolex/ Polycab/ KEI)	110	mtr		
b	Supply,fabrication & fixing of computer board made of 2 nos 5 pin 6 A modular socket & 1 No. 5 pin 16 A socket along with 6A & 16A individual switches having fixed with 1 No.LED indicator and 1 No. board fuse on suitable size GI switch board connection & recessed in wall with mending good all damages as per direction of EIC. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	11	set		
c	Supply,installation,testing & commissioning of Legrand make 32A-3pin wall mounted,industrial type metal clad socket with plug top & 32A SPN MCB control (For UPS Room) (Make - L&T / Anchor-Panasonic/ Crabtree)	4	No.s		
d	Supply laying & connection of UPS incoming power line with 2x10mmsq+1x6mmsq PVC insulated stranded copper wire from PANEL BOARD to UPS incoming power switch. (Make - Havells / Finolex / Polycab/ KEI)	20	mtr		
e	Supplying and fixing 32A change over switch. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	2	No		

SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
10	EARTHING				
a	Earthing installations as per I.E. rules by making earth stations with 600 mm x 600 mm x 6.0 mm. thick copper plate electrode to be installed such that its top edge shall be at a minimum depth. of 3.0 meter below ground level after preparation of ground with charcoal and salt and connecting the MIP with 25 mm x 6 mm G.I. earth lead-in-strip directly in ground by bolting and then brazing to the copper Plate complete with G.I. bolts of suitable length double nuts and washers including supply and fixing of 50 mm dia. partly perforated G.I. pipe with funnel for watering arrangement. 3.0 m. long with 300 x 300 mm. casting plate connection to be fitted with bitumen, the electrode to be driven under G. L. to an av. depth of 3.15 m. The earthing installation should be provided with 300 mm x 300 mm and 300 mm depth inside dimension masonry inspection pit with C.I. hinged cover having locking arrangements, test link of size 150 mm length x 25 mm x 6 mm copper flat connected to copper earth lead-in-strip and restoring the surfaces duly rammed.	1	No.s		
b	Providing and fixing Copper Earth Wire 8 guage in pvc conduit in Floor / walls From earth pit to earthing station & finally connected to Main Panel Board Complete.	42	mtr		
c	Providing and fixing Pipe Earthing (IS 3043 Code) 3.0m. deep with 40 mm. dia. GI pipe With perforations filled with alternate layers of Charcoal and salt. The item includes Funnel on top in brick masonry chamber with CI cover for watering purpose complete.	2	set		
11	MAIN ELECTRICAL CUBICAL PANEL				
	i) 500 V 100 A TPN HRC fuse-1				
	ii) 500V 63A TPN HRC fuse - 1				
	iii) 500V 63A TPN on Load change over switch - 1				
	iv) 500V 100 A bus bar Cu with BBC on heavy duty porcelain				
	v) 500 V 63 A FP MCB-2NO.				
	vi) 230V/415 V 40A(10KA) SP MCB-4No.				
	vii) 230V/415V 25A (10 KA) SP MCB-1 and HAVELLS XPRO				
	viii) 0-100 Amp. Ammeter with selector switch- 1 Set				
	ix) 0-500V Voltmeter with selector switch - 1 set				
	x) 100/5 CT - 3 Nos				
	xi) LED Indicator lamp - 3 Nos				
	xii) Medium pressure caution Board - 1 No.	1	set		



SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
12	Main Incoming Switch Fuse Unit. Supply fixing of 100 Amps TPN HRC type SFU at WBSEB end for main incoming on MS angle. Frame & 02 nos Cable end box including connection.	1	set		
13	COMPUTER DISTRIBUTION BOARD				
	Supply & Installation of following HAVELLS/ LEGRAND make 12 way TPN MCB distribution board with MCB having short circuit breaking capacity of 10KA or RCBO of 100 mA sensitivity having overload short circuit & earth leakage protection complete with neutral,phase & earth bar with 1 No. 40A DP RCBO as incoming 8x6A SPMCB as outgoing to be partially recessed in wall.	1	set		
14	LIGHTING DISTRIBUTION BOARD				
	Supply & Installation of following HAVELLS/ LEGRAND make 16 way TPN MCB distribution board with MCB having short circuit breaking capacity of 10KA or RCBO of 100 mA sensitivity having overload short circuit & earth leakage protection complete with neutral,phase & earth bar with 1 No. 40A DP RCBO as incoming 10x6A SPMCB as outgoing to be partially recessed in wall.	1	set		
15	MAIN POWER CABLE				
a	Supplying, laying & fixing 4 core 50 sqmm PVC insulated,XLPEsheathed AL conductor,1100 v grade armoured cable complete with 2 No.s 8 SWG bear GI wire as running earth(main power cable).	50	mtr		
b	Supplying and fixing compression type gland,brass ring and rubber ring for dust & moisture-proof entry of XLPE/PVC armoured 4 core 50 sqmm cable.	2	Each		
c	Supplying and fixing finishing 50 sqmm cable ends by soldering with cable sockets and insulated tapes etc. including supplying sockets,soldering materials,tapes etc. and making connection to switch,BDB and BBC etc.	2	Each		
16	AC POWER DB and AC POWER POINT WIRING				
a	Supply & installation of following HAVELLS/ LEGRAND make double door VERTICAL TPN POWER DB with 1 No. 63A TPN MCCB as incoming 8x20A SPMCB as outgoing to be partially recessed in wall.	1	Each		
b	Supply and laying 4x10sqmm+1x6sqmm PVC insulated copper wire from Panel board to AC DB (Make - Havells / Finolex / Polycab/ KEI)	30	mtr		
c	Supply and laying 2x4sqmm+1x2.5sqmm PVC insulated copper wire from AC TPN MCB DB to AC power plugs (Make - Havells / Finolex / Polycab/ KEI)	80	mtr		
d	Supply & fixing 20A 3 pin socket with 20 A starter incl. MS box & matching plug point by chase cutting on wall mending good all damages to orginal finish,painting as required for AC's. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand/ Northwest)	6	Each		
e	Supply,fitting,fixing and connecting Bluestar/ Hitachi/ voltas/ carrier make five star 1.5 ton Split A/C including 1 year warranty.				

SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
f	Supply,fitting,fixing and connecting Bluestar/ Hitachi/ voltas/ carrier make five star 1 ton Split A/C including 1 year warranty.				
g	Supply,fitting,fixing and connecting Bluestar/ Hitachi/ voltas/ carrier make five star 0.8 ton Split A/C including 1 year warranty.				
h	Supply and Installation 3CX2.5 sq.mm. Copper Flexible cable for AC indoor to outdoor unit				
i	Supply and Installation 20mm UPVC drain pipe with concil and cementing complete				
17	GENERATOR CABLE				
a	Supplying, laying & fixing 4 core 16 sqmm PVC insulated,XLPE sheathed AL conductor,1100 v grade armoured cable complete with 2 No.s 8 SWG bear GI wire as running earth(main power cable). (Make -Finolex/ Havells/ Mescab/ Polycab/ KEI).				
b	Supplying and fixing compression type gland,brass ring and rubber ring for dust & moisture-proof entry of XLPE/PVC armoured 4 core 16 sqmm cable. (Make - Comet/ Braco/ Jainco)				
c	Supplying and fixing finishing of XLPE/PVC armoured 4core 16 sqmm cable ends by soldering with cable sockets and insulated tapes etc. including supplying sockets,soldering materials,tapes etc. and making connection to switch,BDB and BBC etc. (Make - Comet/ Braco/ Jainco)				
18	SUPPLY ITEMS				
a	Supply of CAT-6, 24 Port Patch Panel of GD Sole/D-Link Make				
b	Supply of 9U. Metal Rack with Glass door.				
c	Supply of CAT-VI 1 Mtr. Patch Cord				
d	Supply of CAT-VI 2 Mtr. Patch Cord				
19	INSTALLATION ITEMS				
a	Installation with crimping of of CAT-6, 24 Port Patch Panel of GD Sole/D-Link Make				
b	Installation with fixing of of 9U. Metal Rack with Glass door.				
20	LIGHTING CUTT OFF :				
	Supply & installing of 32A DP MCB with suitable size metal box complete (for Lighting Cutoff switch near bank entry/exit gate) for 2 nos. LDB CUTT OFF control. (Legrand make)	2	set		
21	UPS MAIN :				
	Supply & installing of 63A 4 pole MCB with suitable size metal enclosure for UPS main control near UPS.	1	set		
22	DISMANTLING OF OLD WIRES				
	Dismantling existing wiring, DB, fixtures etc. (as to be approved by bank) and removing the rubbish and keeping at a place by the bank as per direction of Bank / Architect.	1	Job		
	TOTAL (Rs.)				
In Words () GST EXTRA AS APPLICABLE					

