

# CANARA BANK

## INVITATION TO TENDER

### ONLY FOR EMPANELLED CONTRACTORS

#### OF

### CIRCLE OFFICE KOLKATA

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

ELECTRICAL WORKS

AT

**CANARA BANK – BHIMTALA PRATAPPUR BRANCH**

**[1804]**

TENDER NO.: 41/23-24/PK

NAME OF THE CONTRACTOR: .....

.....

ADDRESS: .....

.....



SEAL & SIGNATURE OF TENDERER

## **NOTICE INVITING THE TENDER**

To,

M/s .....

Sealed tenders on item rate basis are invited from panel Contractors for **Electrical Works at existing premises of BHIMTALA PRATAPPUR Branch.** Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **15.06.2023 till 22.06.2023.**

**Earnest Money Deposit : NIL**

**Period of completion : 30 days**

**Last date, time and place for Submission of tender : On or before 3:00 pm, 22.06.2023 to  
The Assistant General Manager,  
Premises & Estate section  
Canara Bank, Circle Office  
Kolkata**

**Time and date of opening of tender : 3.30 pm on 22.06.2023**

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Assistant General Manager  
Premises & Estate Section  
Canara Bank, Circle Office  
Kolkata**

.....

Date: 15.06.2023



SEAL & SIGNATURE OF TENDERER

### **GENERAL RULES & INSTRUCTIONS TO TENDERERS**

#### **Name of the work: Electrical Works to be carried out at existing premises of BHIMTALA PRATAPPUR Branch**

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

**GST WILL BE PAID EXTRA.**

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 30 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

#### **TENDERS:**

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will



SEAL & SIGNATURE OF TENDERER

be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

#### **AGREEMENT**

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

#### **EARNEST MONEY AND SECURITY DEPOSIT:**

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

#### **CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:**

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents.

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, electrical wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

#### **LIQUIDATED DAMAGES:**

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date



SEAL & SIGNATURE OF TENDERER

**.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.**

**TIME PERIOD FOR COMPLETION: 30 days from the date of award of work.**

#### **FINAL PAYMENTS**

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

#### **ESCALATION:**

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

#### **CONTRACTORS EMPLOYEES:**

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

#### **PAYMENTS:**

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement,



**SEAL & SIGNATURE OF TENDERER**

after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part thereof if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

#### **ARBITRATION:**

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract [other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.



SEAL & SIGNATURE OF TENDERER

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

The arbitrator shall be deemed to have entered on the reference the date he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

**Date:**

**Signature of the Contractor  
With seal and address**



**SEAL & SIGNATURE OF TENDERER**



APPROVED MAKE OF MATERIALS		
1	Switch fuse units (HRC)	LEGRAND / INDO-ASIAN / HAVELLS/L&T
2	Timer (TSQ 100)	L & T / HAVELLS
3	Voltmeter & Ammeter	A. E. / IMP
4	Voltmeter & Ammeter selector switches	KAYCEE / L & T
5	Phase indicating lamp	Vaishno / SIEMENS / ROSS controls
6	Capacitor	CROMPTON/SIEMENS
7	HRC fuses	GE power / SIEMENS / L & T / SCHNEIDER
8	Power Cable : XLPE	GLOSTER/POLYCAB/HAVELLS / NICCO
9	HRC fuse base & carriers.	GE power / SIEMENS / L & T / SCHNEIDER
10	1.1 KV grade PVC insulated armoured aluminium cable (ISI marked)	GLOSTER / NATIONAL / NICCO / HAVELLS
11	1.1KV / 600V grade PVC insulated & sheathed / insulated copper wire & flexible cords (ISI marked).	FINOLEX / HAVELLS
12	RCCB / ELCB / MCCB	LEGRAND / INDO-ASIAN / HAVELLS/L&T
13	Moulded case circuit breaker	LEGRAND / INDO-ASIAN / HAVELLS/L&T
14	RCCB / ELCB	LEGRAND / INDO-ASIAN / HAVELLS/L&T
15	Switch fuse with rewirable fuses. (6A & 32A TPN)	LEGRAND / INDO-ASIAN / HAVELLS/L&T
16	Isolator	LEGRAND / INDO-ASIAN / HAVELLS/L&T
17	Changeover switch (on load type)	LEGRAND / INDO-ASIAN / HAVELLS/L&T
18	MCB distribution board	LEGRAND / INDO-ASIAN / HAVELLS/L&T
19	6/16 Amp modular type switch / flushed type plug socket	ANCHOR (Roma) / CRABTREE / INDO-ASIAN/L&T
20	6/16 Amp modular switch / socket, module plate & mounting M.S. / PVC box.	ANCHOR (Roma) / CRABTREE / INDO-ASIAN/L&T
21	16/25 Amp., 2 module electronic regulator	ANCHOR (Roma) / CRABTREE / INDO-ASIAN
22	Ceiling rose	KAY / EPP / ANCHOR / JJ
23	Holder	KAY / EPP / ANCHOR / JJ
24	Alarm bell	KHERAJ / GETCO
25	Black enamelled Steel conduits (conforming to IS in all respects)	BEC / SUPREME / AKG
26	Compression type brass gland	DOWELLS / JOHNSON / COMET
27	Cable termination socket	DOWELL'S
28	Light fitting & lamps	PHILLIPS / HAVELLS/CROMPTON
29	Ceiling / Wall Mounted Fan	CROMPTON / KHAITAN / HAVELLS/BAJAJ
30	Exhaust fan	CROMPTON / KHAITAN / HAVELLS/BAJAJ
31	Industrial type socket & top	HAVELL'S / CROMPTON / LEGRAND
32	Telephone wire	FINOLEX / RRK/NATIONAL
33	Starters	NORTH WEST / CABTREE
34	All other items not covered above	As per sample approved by Employer/Consultant



SEAL & SIGNATURE OF TENDERER



**COST ESTIMATION WITH SCHEDULE OF SPECIFICATIONS AND QUANTITIES FOR ELECTRICAL WORKS OF BHIMTALA PRATAPPUR BRANCH --- CANARA BANK , UNDER KOLKATA CIRCLE**  
(ESTIMATE MODIFIED BY SECTION 07.06.2023)

SL.no	DESCRIPTION OF ITEMS	UNIT	QTY	RATE	AMOUNT
1	<b>POINT WIRING (FRLS wires to be used)</b>				
a	Wiring for the following light wall fan exhaust fan, call bell points with 1.5 sqmm PVC insulated stranded Cu conductor wire in concealed / exposed medium grade ISI marked PVC conduits as called for in specification including providing 1 sqmm insulated Cu earth wire including cost of circuit wiring from DB to the point with 2x2.5 sqmm + 1x1.5 sqmm complete with providing and fixing of accessories like saddles, clamps, flexible pipes, dash fasteners etc. modular switches with face plates, switch boxes, grid plates are included in the above rate.				
	1. Primary points	nos	12		
	2. Loop points	nos	8		
	3. Primary point (wall and exhaust fan controlled by 1 switch and one 5 Amp. socket)	nos	15		
	The above work includes extensions of points with flexible conduits as reqd. to table bottoms etc. as reqd.				
b	Wiring for 5Amp light plug point with 2 x 2.5 sq mm + 1 x 1.5 sqmm PVC single core copper wire in PVC polythene pipe with galvanized iron junction & switch boxes & clip in type, 6 Amp modular type switches, 5Amp socket with all accessories, T&P & as directed by the Engineer-in-charge at counter table, maximum 6 points per circuit.	nos	10		
c	Wiring of 15 Amp power sockets with switch on separate board with 2 x 4 sq mm + 1 x 1.5 sqmm PVC single core copper wire in PVC Super polythene pipe with galvanized iron junction & switch boxes & clip in type 6 Amp modular type switches with all accessories, T&P & as directed by the Engineer-in-charge at counter table, maximum 6 points per circuit. (Location: Pantry -1, water cooler - 1, Manager cabin for for winter - 1, for each two counter one- 2, cash cabin - 1)	nos	8		
	Supplying, fitting and fixing 4 nos-2 TR, 3 nos- 1TR machines with all outdoor fittings and fixtures, including copper refrigerant piping, electrical cabling between indoor and outdoor unit, pvc drain piping --- HITACHI / DAIKIN MITSUBISHI --- (AC MACHINES TO BE SUPPLIED BY THE BANK)	nos	0		
d-2	Wiring for Air Conditioners point with 2x4+4 sqmm PVC insulated copper conductor wire of 650/1100 volts grade with PVC insulated copper earth wire in concealed / exposed PVC pipe, including Concealed Industrial Metallic Socket with 20/32Amp SP MCB housed in MS sheet box with PVC insulated Copper earth wire. Work is also including circuit wiring & cutting chases and making good the surfaces wherever required. (Circuit Shall not be paid extra) There must be separate circuit wiring for each point & this circuit wiring must not be paralled looped with switch board of light plug points. Please Note that metallic socket for ATM to installed in coordination with Furnishing vendor [Note:- No AC points & Electrical point should be made inside ATM room]	nos	5		
e	Wiring for UPS power socket with 2 x 2.5sq mm + 1x1.5 sqmm PVC single core copper wire in PVC polythene pipe with galvanized iron junction & switch boxes & clip in type including 3 nos. 5 amp. sockets 1 no. 16 amp. switch, One indicator modular type with grid and face plates modular type, (maximum three stations per circuit).	nos	11		
	Concealed conduit wiring to call bell point with one gong bell of 6" dia placed at strategic point with 6 Amp switch bell push clip in type modular type fixed on G.I. boxes placed at skirting level for emergency use, the wiring details are as per Sr. no. - 01. The places as located in drawing & as per direction of Engineer-in-charge.	set	1		



2	<b>DISTRIBUTION BOARDS</b>				
	Distribution boards: Design, manufacture, supply, of 1.6 mm th. Sheet steel fabricated surface recessed mounted, vertical configuration, double door type, distribution boards ( factory made with powder coating )				
A	<b>DB for normal Lighting and Power</b>				
	4 way TPN DB with				
	Incoming :				
	40A 4 Pole MCB				
	Outgoing :				
	8 nos SPMCB	nos	1		
B	<b>DB for Airconditioning</b>				
	4 way TPN DB for AC with				
	Incoming :				
	63A 4 Pole MCB				
	Outgoing :				
	6 nos SPMCB	nos	1		
C	<b>DB for UPS Input</b>				
	4 way TPN DB for AC with				
	Incoming :				
	40 A 4 Pole MCB ---1 no				
	Outgoing :				
	60 A DP MCBs ----- 1 no	nos	1		
3	<b>UPS Output</b>				
	40A DP MCB in MS box ( for UPS OUTPUT in UPS room )	Set	1		
4	<b>UPS DB</b>				
	Distribution boards 1 No. 60A 2 pole MCB isolator				
	Out going 10 Nos. 6/10 SP MCB s ( for UPS distribution boards)	set	1		
5	<b>SUB MAINS WIRING - ( FRLS wires to be used )</b>				
	Supply of all required materials and wiring to submains with following number and sizes of PVC insulated 1100 volt grade standard copper wire run inside pre-laid PVC conduit pipe of ISI mark as required and copper wire as earth continuity conductor and complete in all respect including making good to all damages caused and as per the direction of Consultant and Engineer-in-charge.				
a	2 x 4 sqmm + 1 x 2.5 sqmm Cu wire general ( for Light and Power DB )	mts	120		
b	4 x 16 sqmm + 1 x 2.5 sqmm Cu wire general ( for AC DB )	mts	60		
c	4 x 10 sqmm + 1 x 4 sqmm Cu wire general ( for UPS supply )	mts	50		
d	2 x 6 sqmm + 1 x 2.5 sqmm Cu wire general ( from UPS room to DB )	mts	15		
e	Supplying and laying 2 x 2.5 sqmm Cu. Wire in PVC conduit from panel to Glow Sign board	nos	2		
6	<b>EARTHING</b>				
a	Providing and fixing of chemical earth electrode made out of 50mm dia class-B Asaha lock or equivalent 2m length with copper plate made out of 600 x 600 x 3.15 mm tinned copper plate along electrode with one number 40 x 5mm tinned copper strip grazed with the plate buried vertically with top edge of the plate at a depth of 1500 mm with arrangements for termination of copper strip of earth continuity conductor including cost of charcole, saltoreign soil, water pouring arrangements brick massionry encloser on top with R.C.C cover complete with labour and material as per direction of Engineer-in-charge as per IS:3043 1987 ( for UPS , panel board and ATM )	set	1		
b	do as above with 600 mm x 600 mm x 6 mm th. G.I plate ) for MAIN PANEL ) ( 1 for BRANCH , 1 for UPS and 1 for ATM )	set	1		



	<b>EARTH STRIPS / WIRES</b>				
	Supply, installation, effecting proper connection, testing, and commissioning of the following size CU, G.I earth strip + wire or in recess as reqd.				
a.	10sqmm insulated Cu. Earth wire in PVC conduit pipe (for UPS)	rmt	60		
b.	8mm dia G.I earth wire	rmt	60		
8	<b>FITTINGS AND FIXTURES</b>				
a.	Supply, installation and testing of recess LED lights fittings (36 Watt) of square type - 2' x 2' with all accessories complete of Philips - Havells make as required as per direction of Engineer in charge.	nos	11		
	Supply, installation and testing of recess LED light fittings Nos. ( 15 16 watt) of round type - 6" dia with all accessories complete of Philips Crompton Wipro make as required as per direction of Engineer in charge.	nos	10		
c.	Supply, installation and testing of single tube lights T5 patty Nos fittings (36 watt) - LED type of surface mounting with all accessories complete of Philips Crompton Wipro make as required as per direction of Engineer in charge.	nos	8		
	Providing and fitting of 450 mm sweep Wall mounted fan of approved make	nos	9		
	Providing and fitting of 1200 mm sweep ceiling fan of approved make.	nos	3		
	Providing and fitting of 400 mm sweep cabin fan of approved make.	nos	1		
e.	Providing and fitting of 400 mm sweep Exhaust fan of approved make, for UPS room and toilets	nos	3		
b.	Providing and fitting of call bell of approved make.	nos	1		
f.	Providing and fitting LED Batten Light - 2' length for cash counter-- 8W and toilets	nos	4		
g.	Providing and fitting of modular fan regulator of approved make.	nos	3		
9	<b>PHONE WIRING.</b>				
a.	Supplying, Installation, Testing & Commissioning of 10 pair 0.51 sq. mm. telephone unarmoured cable in 20 mm PVC pipe. (Make - Finolex / Havells Polycab)	50.00	r. m.		
b.	Supply, installation, testing & Commissioning of Telephone point with 1 No. of RJ-11 socket, 1 Module Plate & Modular Box as per instructions of the Architect.	3.00	unit		
b ii.	SET Commissioning of telephone Junction box 10 pair krone type housed in MS box with Lock & key.	1.00	unit		
10	<b>MAIN PANEL BOARD</b>				
	Supply, delivery, installation, testing, commissioning, of L&T indoor wall floor mounted type distribution boards made out of 2 mm thk. CR sheet metal duly acid treated primed & painted with 2 coats of enamel paint compartment arrangement for each equipment & bus bar chamber on the top of the panel running horizontal through out its length duly lamp, vermin proof having provision cable by conduit entry, earthing stud as per specification mentioned below duly factory wired conforming to the relevant ISS & as per special condition of contract, making good the damages M.S. Cubical type Panel board should have hinged door at the front. The panel shall be provided with all accessories & following arrangements complete in all respect & direction of EIC (before fabrication of panel board drawing is to be approved by Engineer-in-charge).	set	1		
	125 Amp TP MCCB --1 no				
	0-500V CTs --3 nos				
	3 nos. indication lamps with 3 fuses --1 set				
	125 A 4P copper bus bar ---1 set				
	100A -4P MCCB for BRANCH --- 1 SET				



	63 A - 4P MCCB for ATM --- 1 SET				
	63A - 4P MCCB for AC --- 1 SET				
	1 No 100 A- HRC FSU, with rewirable fuse links for generator				
	<b>Outgoing -</b>				
	100 A 4P Change over switch --1no				
	63A 4P MCB ---1 no				
	63A DP MCB ---1 no				
	<b>Outgoing- 1 No 63A DP MCB for A.C</b>				
	1 No 40 A TPN MCB for A.T.M				
	1 No 63 A DP MCB for U.P.S incomer and outgoing				
	1 No 40 A DP MCB for LDB PDB. 40A DP MCB Spare				
	1 No 32 A DP MCB for Glow sign board (1 spare )				
	1 No. VAF Digital meter with CT.				
<b>b</b>	<b>SWITCH NEAR METER</b>				
	Providing and fixing 200Amp MCCB in 16 gauge sheet cubicle box. of L.T DH -200 25KA (near meter ) complete with incoming and outgoing connections.	set	1		
<b>12</b>	<b>TIMER</b>				
	Supply & installation of Timer Box for Glow sign Supply comprising of the following : ( 1	set	2		
	FOR BRANCH and 1 FOR ATM )				
	1 no SP MCB				
	1 Nos 25A rated Contactor				
	1 no 24 Hours Timer				
<b>13</b>	Supply and erection of earth bus on wall ( min. length 0.3 mtr.) on insulator with drilled holes on the bus with GI bolt , nut , washer etc for the following:-				
<b>a</b>	With (25x3) mm CU flat	each	2		
<b>14</b>	Making temporary arrangement of electrical and LAN line to make the branch functional		L.S		
<b>15</b>	Supply & installation of 2 nos. 32A DP Changeover switch to be fixed and complete with one no.60A rated copper Bus bar for changing supply from one UPS to another with all accessories.	set	2		
<b>16</b>	Marking of all DB's & Main switches' Change over and power outlet points	job	1		
<b>17</b>	<b>DISTRIBUTION CABLE</b>				
<b>A</b>	<b>Supply &amp; lay 1.1 KV grade PVCA AL cable on wall having MS /HDP pipe protection near floor level and clamping as required for the following:-</b>				
<b>a</b>	35 Sq mm 4 core Cu with 2 nos 10 SWG GI wire-MAIN CABLE	20	Mtr		
<b>b</b>	16 Sq mm 4 core Cu with 2 nos 10 SWG GI wire ---CABLE for generator	25	Mtr		
<b>d</b>	2.5 sq mm 2 core CU for UPS Plate Earthing	25	Mtr		
<b>e</b>	2 nos. 35 sq. mm. CU flexible wire through GI flexible pipe complete with end termination with CU sockets.	8	Mtr		
	( Meter loop connection with Main SFU & Busbar)				
<b>B</b>	<b>Making end termination of 1.1 KV grade PVCA Al cable with supply of cable end box , brass Gland, CU crimping socket &amp; jointing materials as required for the following:-</b>				
<b>a</b>	35 Sq mm 4 core Cu	2	Each		
<b>b</b>	16 Sq mm 4 core Cu	2	Each		
<b>18</b>	Dismantling existing wiring / DB / light fittings / fan, any types of electrical work etc. and removing the rubbish outside the compound for auctioning complying local municipal rules as per direction of Bank Architect.	1	L.S		
	<b>TOTAL (Rs.)</b>				
	<b>GST EXTRA AS PER GOVT. NORMS ----- 18%</b>				

